

GREENWOOD LOCAL STRUCTURE PLAN

MARCH 2015




Government of **Western Australia**
Department of **Housing**

OPENING DOORS
To Affordable Housing



A member of
FRASERS CENTREPOINT



CONTENTS

PART ONE STATUTORY SECTION

1.0	STRUCTURE PLAN AREA	10
2.0	STRUCTURE PLAN CONTENT	10
3.0	INTERPRETATION AND SCHEME RELATIONSHIP	10
4.0	OPERATION	10
5.0	LAND USE AND SUBDIVISION REQUIREMENTS	10
5.1	Land Use Permissibility	10
5.2	Residential	10
5.2.1	Dwelling Target	10
5.2.2	Density	11
5.3	Public Open Space	11
5.4	Conditions of Subdivision Approval	11
6.0	DEVELOPMENT REQUIREMENTS	11
6.1	Local Development Plans	11
6.2	Residential Design Codes Variations	11

PART TWO EXPLANATORY SECTION

1.0	PLANNING BACKGROUND	14	2.0	SITE CONDITIONS AND CONSTRAINTS	23
1.1	Introduction	14	2.1	Biodiversity and Natural Area Assets	23
1.1.1	Purpose	14	2.2	Landform and Soils	24
1.1.2	Background.....	14	2.2.1	Landform	24
1.2	Land Description	16	2.2.2	Soils	25
1.2.1	Regional Context	16	2.2.3	Acid Sulfate Soils.....	25
1.2.2	Local Context	16	2.3	Groundwater and Surface Water	25
1.2.3	Area and Land Use	18	2.4	Water Management and Conservation	25
1.2.4	Legal Description and Ownership	18	2.5	Bushfire hazard	25
1.3	Planning Framework	19	2.6	Heritage and Site History	26
1.3.1	Zoning and Reservations.....	19	2.7	Existing and Surrounding Community	27
1.3.2	Planning strategies and policies.....	20	2.8	Community Consultation	28
1.3.3	Relevant Approvals, Recent Decisions and Pending Framework Changes	22	2.8.1	Overview.....	28
			2.8.3	Community Ideas Day and Public Consultation Period	29
			2.8.4	Greenwood East Working Group	30
			2.8.5	Key Outcomes from Community Consultation Process.....	30

CONTENTS

3.0 LAND USE AND SUBDIVISION REQUIREMENTS	33
3.1 Sustainable Development Outcomes	33
3.2 Urban Design Principles	34
3.3 Illustrative Masterplan	36
3.4 Built Form and Delivery	38
3.5 Interface with abutting residential	42
3.6 Open space and management	44
3.6.1 Open Space Distribution And Calculation	44
3.7 Landscape masterplan and open space design	46
3.8 Crime protection through environmental design (CPTED)	48
3.9 Residential Density and Height	49
3.10 LAND TENURE ARRANGEMENTS	51
3.11 Education facilities	51
3.12 Employment	52
3.13 Streets and movement	52
3.13.1 Movement network hierarchy	52
3.13.2 Pedestrian	54
3.13.3 Cycling	54
3.13.4 Public transport	54
3.13.5 Private vehicles and traffic	55
3.14 Water management	56

3.15 Infrastructure coordination, servicing and earthworks	56
3.15.1 Site Works	56
3.15.2 General earthworks	56
3.15.3 Infrastructure coordination & servicing ..	56
3.16 Developer contribution arrangements	57
3.17 Implementation	57
3.17.1 Further documentation and management plans	57
3.17.2 Land assembly	57
3.17.3 Indicative staging	57

PART THREE TECHNICAL APPENDICES

Appendix 1: Pre-Lodgement Consultation Summary
Appendix 2: Consultation Plan
Appendix 3: Arboriculture Assessment
Appendix 4: Environmental Summary Report
Appendix 5: Geotechnical Report
Appendix 6: Traffic Impact Assessment
Appendix 7: Landscape Masterplan
Appendix 8: Local Infrastructure and Servicing Strategy

CERTIFIED THAT AGREED STRUCTURE PLAN/20.....
WAS ADOPTED BY RESOLUTION OF THE WESTERN AUSTRALIAN PLANNING COMMISSION ON.....

.....
Chairman, Western Australian
Planning Commission

AND BY

RESOLUTION OF THE COUNCIL OF THE CITY OF JOONDALUP ON

AND THE SEAL OF THE MUNICIPALITY WAS PURSUANT TO THE COUNCIL'S RESOLUTION HEREUNTO AFFIXED IN THE PRESENCE OF:

.....
Mayor, City of Joondalup

.....
Chief Executive Officer, City of Joondalup

TABLE OF MODIFICATIONS

Modification no.	Description of modification	Date endorsed by Council	Date endorsed by WAPC

EXECUTIVE SUMMARY

Item	Data	Section number referenced within the structure plan report
Total area covered by the structure plan	3.8636 hectares	Part 2 Section 1.2.4
Area of each land use proposed:		Part 2 Section 3.6.1
_Residential	3.0393 hectares	
_Industrial	0	
_Commercial	0	
Estimated lot yield	95-100 lots	Part 2 Section 3.4
Estimated number of dwellings	115 - 135 dwellings	Part 2 Section 3.4
Estimated population	250-270 people	Part 2 Section 3.4
Number of high schools	0	Part 2 Section 3.11
Number of primary schools	0	Part 2 Section 3.11
Estimated area of open space	25%	Part 2 Section 3.6.1

This Local Structure Plan report has been prepared on behalf of Australand and the Department of Housing, the sentiment is understood, however the City remains the assessing body of the structure plan, in order to accommodate urban residential development on the former East Greenwood Primary School site. The LSP establishes a layout for the local road network, residential development sites and open spaces that is coordinated and integrated with surrounding development.

The strategic intent of the project is for the Department of Housing, working in partnership with the private sector, to deliver a showcase infill development that leverages from the strengths of each party. This will provide the East Greenwood community with a result that not only delivers a diversity of housing options for a range of incomes but also adds value to its existing surrounds.

The Department of Housing welcomes this partnership with Australand as an opportunity to give the people living, working and contributing to the East Greenwood community, new housing stock that meets their needs – from downsizers to first home buyers – and does so in a way that encourages them to explore and connect with the enhanced amenities that the development will provide.

The Local Structure Plan design is the result of a rigorous pre-lodgement community consultation process, involving a Community Idea's Day, a community feedback submission period, the establishment of a Community Working Group, and the opportunity to share and interact by way of a dedicated social media Facebook page. A total of 966 comments were received through these processes, with the Community Working Group, comprised of 12 active members, contributing to the ultimate design and decision making process.

The project team responsible for the preparation of this Local Structure Plan are:

- RobertsDay; Town Planning and Urban Design.
- Australand; Development Partner, Building Design and Construction Manager.
- Department of Housing; Developer and Proponent.
- Community Working Group; Strategic Advice and Guidance.
- RPS; Environmental Consultants.
- Emerge; Landscape and Water Management.
- Transcore; Transport Engineers.
- JDSI; Servicing Engineers.



PART ONE

STATUTORY SECTION

PART ONE: STATUTORY SECTION

1.0 STRUCTURE PLAN AREA

The provisions of the Local Structure Plan (LSP) apply to Lot 9867 (63) Mulligan Drive, Greenwood being the land contained within the inner edge of the line denoting the Structure Plan boundary on the Structure Plan Map (Plan 1).

2.0 STRUCTURE PLAN CONTENT

The LSP comprises three parts;

- a. Statutory Section (Part 1);
- b. Explanatory Section (Part 2); and
- c. Appendices – Technical Reports.

3.0 INTERPRETATION AND SCHEME RELATIONSHIP

Unless otherwise specified in this part, the words and expressions used in the LSP shall have the respective meanings given to them in the City of Joondalup District Planning Scheme No. 2 (the Scheme) including any amendments gazetted thereto.

Pursuant to clause 9.8 of the Scheme:

- a. The provisions, standards and requirements specified under Part 1 of this LSP shall have the same force and effect as if it were a provision, standard or requirement of the Scheme. In the event of there being any variations or conflict between the provisions, standards and requirements of this LSP, then the provisions, standards and requirements of this LSP shall prevail.
- b. Any other provision, standard and requirement of Part 1 of the LSP that is not otherwise contained in the Scheme, shall apply to the land as though it is incorporated into the Scheme, and shall be binding and enforceable to the same extent as if part of the Scheme.
- c. Part 2 of this LSP and the Appendices – Technical Reports are to be used as reference only to clarify and guide interpretation and implementation of Part 1.

4.0 OPERATION

In accordance with clause 9.8.1 of the Scheme, this Structure Plan shall come into operation when it is certified by the Western Australian Planning Commission (WAPC) pursuant to subclause 9.6.3 of the scheme.

5.0 LAND USE AND SUBDIVISION REQUIREMENTS

The LSP Map (Plan 1) outlines land use, zones, and reserves applicable within the LSP area.

The zones and reserves designated under this LSP apply to the land within it as if the zones and reserves were incorporated into the Scheme.

5.1 LAND USE PERMISSIBILITY

Land use permissibility within the Structure Plan areas shall be in accordance with the corresponding zone or reserve under the Scheme.

5.2 RESIDENTIAL

5.2.1 Dwelling Target

- a. Objective:
To provide a minimum of 115 dwellings within the LSP area.
- b. Subdivisions to achieve the following:
Density in accordance with the Residential Density Code depicted on the Structure Plan Map (Plan 1).

PART ONE: STATUTORY SECTION

5.2.2 Density

Plan 1 defines the residential density code that applies to specific areas within the Local Structure Plan.

5.3 PUBLIC OPEN SPACE

Public open space shall be provided across a minimum of 10% of the LSP area. Public Open Space is to be provided generally in accordance with Plan 1.

5.4 CONDITIONS OF SUBDIVISION APPROVAL

At the time of subdivision the following conditions may be recommended, as applicable, requiring preparation and/or implementation of the following strategies:

- i. Urban Water Management Plan (City of Joondalup; Department of Water)

6.0 DEVELOPMENT REQUIREMENTS

6.1 LOCAL DEVELOPMENT PLANS

Local Development Plans are to be prepared in accordance with clause 9.12 of the Scheme, prior to any subdivision and/or development, for all lots subject of the LSP area (Plan 1).

6.2 RESIDENTIAL DESIGN CODES VARIATIONS

Table 1 sets out variations to the Residential Design Codes that constitute deemed-to-comply development within the Structure Plan area and which do not therefore require neighbour consultation and subsequent planning approval. Local Development Plans may grant further variations to the Residential Design Codes, subject to City of Joondalup approval.

TABLE 1_ RESIDENTIAL DESIGN CODE VARIATIONS

	Open Space Min total (% of site)
R40	As per R-Codes
R60	25 %
R80	25 %



REILLY RD

R60

R80

R60

R80

R80

R60

SWIFTS ST

MULLIGAN DRIVE

DARGIN PL

R40

R80

LEGEND

LOCAL SCHEME RESERVES

 PARKS AND RECREATION

ZONES

 RESIDENTIAL

OTHER

 STRUCTURE PLAN BOUNDARY

 R CODES

 INDICATIVE ROAD RESERVE BOUNDARY

 INDICATIVE PAVEMENT SURFACE

PART TWO

EXPLANATORY SECTION

PART TWO: EXPLANATORY SECTION

1.0 PLANNING BACKGROUND

1.1 INTRODUCTION

1.1.1 Purpose

This Local Structure Plan (LSP) has been prepared to facilitate residential development of the former East Greenwood Primary School site at 63 Mulligan Drive, Greenwood.

The purpose of the explanatory section of the LSP report is to provide background on the design of the LSP; an overview of features on the site and its context; indicative design of the ultimate urban form; compliance with relevant planning requirements; and details for project implementation. In particular, the LSP report demonstrates how the design has been formulated based on a concerted community consultation and feedback process.

Technical reports, contained in Part Three, are summarised in this part also.

1.1.2 Background

The land subject of this LSP has a rich history dating back to 1972 when the suburb of Greenwood was originally subdivided by the Parin family. At this time, the site was designated for educational use by the State Government, with the East Greenwood Primary School built to service residents of the Greenwood locality.

In June 2007 the Department of Education and Training (DET) advised the City of Joondalup that the East Greenwood Primary School was surplus to its requirements and of its intention to collocate it with the services provided at Allenswood Primary School. The DET also announced that it intended to sell the site to the Department of Housing (DoH) for the purposes of providing an innovative development catering for a range of housing needs including, social housing, affordable rental and home ownership options. In 2009 the DET initiated a scheme amendment with the City of Joondalup to rezone the land from Public Purposes to Urban Development. The rezoning was gazetted in December 2010.

The primary school ceased operating in September 2010 and the buildings were subsequently demolished and removed in May and June 2011.

A contract for sale was executed in 2011 and the DoH sought a private sector development partner by way of an Expression of Interest Process. Australand was awarded the tender to partner with DoH in July 2013.

Refer Figure 1, Aerial Photograph.

PART TWO: EXPLANATORY SECTION

FIGURE 1: AERIAL PHOTOGRAPH



PART TWO: EXPLANATORY SECTION

1.2 LAND DESCRIPTION

1.2.1 Regional Context

Regionally, the LSP area is approximately 17 kilometres north of the Perth city centre and situated within the Greenwood locality. The LSP area is approximately 7.0 kilometres east of Hillarys Boat Harbour, and 9.5 kilometres south of the Joondalup city centre.

The LSP area is within the City of Joondalup municipality.

1.2.2 Local Context

Locally, the LSP area is approximately 680 metres south of Lake Goollelal and 750 metres north of Warwick Open Space. The LSP area is approximately 580 metres south of Hepburn Avenue, 260 metres west of Wanneroo Road, and 670 metres north of Warwick Road. The Mitchell Freeway is approximately 2.5 kilometres to the west of the LSP area.

The LSP area is bounded by Dargin Place to the west, Reilly Way to the north, and Mulligan Drive to the east. Cockman Park shares part of the site's southern boundary. The heavily vegetated park contributes to Greenwood's character and amenity, but contains limited facilities.

The LSP area is serviced by the Greenwood Primary School, which is a combination of the former East Greenwood Primary School and Allenswood Primary School. Greenwood Primary School is approximately 750 metres west of the LSP area. Additionally, the Marangaroo Primary School is approximately 750 metres east of the LSP area, but outside the school's 'intake area' as defined by the Department of Education. In Semester 2 of 2014, the Department of Education's database listed 327 enrolled students for Greenwood Primary School, with a capacity of 465 students. Capacity is likely to be further expanded when grade 6 and 7 students transition to secondary education facilities in 2015.

The Kingsway Shopping Centre services the broader Greenwood locality from a retail and employment standpoint, and is approximately 800 metres north east from the LSP area. Warwick Leisure Centre services the broader Greenwood locality, and is approximately 860 metres south of the LSP area.

Bus services currently run along Cockman Road, approximately 150 metres to the west of the LSP area, and Wanneroo Road, approximately 300 metres to the east. Transperth Bus Service 447 operates on Cockman Road and connects the LSP area with Warwick Station to the south and Whitfords Station to the north. Transperth Bus Services 389 and 450 operate on Wanneroo Road and connect the LSP area with Warwick Station, the Perth CBD, and the Wanneroo City Centre to the north. Greenwood Train Station is located approximately 3 kilometres west of the LSP area, and has a 'Park and Ride' facility. The public transport services connect the LSP area with the broader Perth Metropolitan Region.

Refer Figure 2, Local Context.

PART TWO: EXPLANATORY SECTION

LOCAL CONTEXT




FIGURE 2: LOCAL CONTEXT

PART TWO: EXPLANATORY SECTION

1.2.3 Area and Land Use

The Greenwood locality is typically characterised by low-density single detached residential dwellings. Some examples of grouped dwelling duplex developments exist and are scattered throughout the locality. Small-scale vehicle orientated commercial uses are located on Wanneroo Road, approximately 150m east of the site.

Cockman Park is the home of Perth Disc Golf Club, accommodating a '9 basket' course. The school car park was historically utilised by disc golfers, being located near the 'first basket' to the south east of the site.

Following demolition of the buildings and structures associated with the former school use in mid 2011, the LSP area has been left vacant. Unfettered pedestrian access to the LSP area has existed since this time. Community feedback suggests that the site has been mostly used for dog walking and disc golf parking.

The LSP area has large cleared areas of planted lawn with stands of parkland cleared trees, predominantly to the north west and central areas of the site.

The topography of the LSP area is generally uniform with the gradient slightly decreasing from approximately 37.6m AHD (Australian Height Datum) in the site's south-west to a minimum of approximately 33.4m AHD in the north-east and north west corners.

1.2.4 Legal Description and Ownership

The LSP area involves one lot as detailed in Table 1 below.

TABLE 1: LAND DETAILS

Lot no.	Street Address	CT Volume-Folio	Deposited Plan no.	Area
9867	63 Mulligan Drive, Greenwood	2741-295	47280	3.8636 ha

PART TWO: EXPLANATORY SECTION

1.3 PLANNING FRAMEWORK

1.3.1 Zoning and Reservations

1.3.1.1 Metropolitan Region Scheme

Under the provisions of the Metropolitan Region Scheme (MRS) the LSP area is zoned 'Urban'.

1.3.1.2 City of Joondalup

Under the provisions of the City of Joondalup District Planning Scheme No. 2 (DPS2) the LSP area is zoned 'Urban Development'. Land subject to an Urban Development zone may not be developed or subdivided unless it is in accordance with an endorsed structure plan.

The LSP area is generally surrounded by land zoned 'Residential' with an applicable density code of 'R20'. Cockman Park, immediately abutting the LSP area to the south, is reserved for 'Parks and Recreation' under DPS2.

Refer Figure 3, DPS2 zoning map.

FIGURE 3: DPS2 ZONING MAP



LOCAL SCHEME RESERVES



ZONES



OTHER



PART TWO: EXPLANATORY SECTION

1.3.2 Planning strategies and policies

1.3.2.1 *Directions 2031 and Beyond*

Directions 2031 and Beyond (Direction 2031) provides the State with a strategic plan and spatial framework for the metropolitan Perth and Peel region. Directions 2031 establishes a vision for future urban growth, addressing population growth and land use patterns with a view to accommodating a projected increase of more than half a million people in Perth and Peel by 2031. Further, the strategy recognises that planning for the Perth and Peel region will need to accommodate 3.5 million people by 2056 almost doubling the current population.

Directions 2031 proposes a strong role for urban infill and consolidation to accommodate this increase in population, and identifies the importance of established suburbs in contributing to meeting this demand.

1.3.2.2 *Draft Outer Metropolitan Perth Sub-Regional Strategy*

The Draft Outer Metropolitan Perth Sub-Regional Strategy (Sub-Regional Strategy) provides further guidance for the outer metropolitan regions, categorised into four growth sub-regional areas. The LSP area falls within the North-West Sub-regional Area, which comprises the Wanneroo and Joondalup municipalities.

The Sub-Regional Strategy recognises that the City of Joondalup has limited capacity to provide growth in unconstrained land, as many former greenfield land banks have now been developed. As such, the focus shifts to infill and redevelopment opportunities in order to satisfy the identified need to accommodate a further 167,400 dwellings within the North-West Sub-regional Area. More specifically, the Sub-Regional Strategy recommends that 12,700 dwellings can be provided in infill areas within the Joondalup municipality. A function of the development of the LSP area will be to contribute to this infill dwelling target.

1.3.2.3 *State Planning Policy No. 3: Urban Growth and Settlement*


State Planning Policy No. 3: Urban Growth and Settlement (SPP3) applies to the whole of the State in promoting sustainable and well planned settlement patterns that have regard to community needs and are responsive to environmental conditions. The objectives and principles of Directions 2031 and Liveable Neighbourhoods are enshrined in this Policy.

SPP3 recognises that the majority of new development in metropolitan Perth has been in the form of low density suburban growth. This form of development intensifies pressure on valuable land and water resources; imposes costs in the provision of infrastructure and services; increases the dependence on private cars; and creates potential inequalities for those living in the outer suburbs where job opportunities and services are limited.

Accordingly, the Greenwood LSP, which provides a consolidated urban form, while delivering amenity and reducing car dependence, is consistent with the framework stipulated in SPP3.

PART TWO: EXPLANATORY SECTION

FIGURE 4: CITY OF JOONDALUP LOCAL HOUSING STRATEGY



1.3.2.4 City of Joondalup Local Housing Strategy

The City of Joondalup Local Housing Strategy reviewed the existing housing stock and density in the City to identify opportunities to meet its Direction 2031 target of 12,700 dwellings in infill areas only. The study presented a number of key findings relevant to the LSP area, including:

Key findings

- Changing household structure will place pressure on current/existing housing supply. Providing a greater range of housing products will not only help alleviate these pressures but also go some way towards providing housing which is more affordable for singles, young couples, and the aged.
- The two factors of an ageing population and falling household sizes will be the key drivers influencing the size, direction and composition of the housing market in the City of Joondalup.
- The housing products currently available in the City do not reflect the emerging demographic trends predicted for the City. It is imperative to ensure a balanced mix of housing to avoid a mis-match between housing demand and supply.
- Limited 'land bank' opportunities for future housing exist within the City. In order to cater for future demands it is necessary to provide housing in infill areas.
- A high standard of redevelopment in infill areas will have a positive impact on streetscapes and residential amenity.
- More compact housing should be provided in order to deliver a wider range of housing to meet the social and economic needs of changing demographics in the City.
- Recognises the ability of larger 'opportunity sites' to provide a new compact form of development which will alleviate pressure from existing low density suburban areas, where it is desirable to maintain this density to accommodate family living arrangements.

PART TWO: EXPLANATORY SECTION

Recommendation 7 of the Local Housing Strategy emphasises the need for larger “opportunity sites” to deliver a ‘target’ density in accordance with the State Government policy framework. Following the strategic direction set by the State in Directions 2031, the intent is for “opportunity sites” to achieve a minimum average density of 25 dwellings per site hectare. This target is to ensure the broader objective of Directions 2031, being 15 dwellings per gross urban hectare, is achieved.

The LSP area is explicitly identified as a ‘Future Development Site for Housing’ under the Local Housing Strategy, which falls within the “opportunity site” description as referenced in the above Key Findings summary.

Refer Figure 4, City of Joondalup Local Housing Strategy.

1.3.2.5 City of Joondalup Height and Scale of Buildings within Residential Areas Policy

The City’s Height and Scale of Buildings within Residential Areas Policy (Height Policy) stipulates a maximum height limit of 8.5 metres, with the exception of minor projections such as air conditioning units, pergolas, screens etc. At the time of writing, following concerns raised in the recently adopted Local Housing Strategy, the City is reviewing the Height Policy with a view of increasing the maximum limit for opportunity sites. Notwithstanding, Local Development Plans provide the City with the opportunity to modify height limits.

1.3.3 Relevant Approvals, Recent Decisions and Pending Framework Changes

1.3.3.1 Relevant Ministerial Announcements

2007 – Minister for Education and Training announces plans to decommission the East Greenwood Primary School site and sell the site to the DoH for the purposes of urban development.

2010 – Minister for Housing announces that the DoH would seek to “deliver an innovative solution with a private sector partner and intends to engage the market through an Expression of Interest Process... with a preferred partner to be selected in August 2011. The partner will ensure the development comprises social housing, affordable rental and home ownership options.”

1.3.3.2 Proposed Amendment No 73 to DPS2

Proposed Amendment No 73 to DPS2 (Amendment 73) will implement the majority of the recommendations made in the City’s Local Housing Strategy. Relevant to the LSP area, Recommendation 7 of Amendment 73 states:

“It is proposed that a minimum residential density of 25 dwellings per site hectare be required for the development of lots one hectare or greater within the ‘Residential’ zone, as well as for development within the ‘Urban Development’ zone where a structure plan is required to be prepared.”

At the time of writing, the City is conducting a public consultation period with the final submission date being 10 December 2014. Amendment 73 would require the endorsement of the WAPC and subsequent final approval from the Minister of Planning prior to gazettal.

PART TWO: EXPLANATORY SECTION

2.0 SITE CONDITIONS AND CONSTRAINTS

2.1 BIODIVERSITY AND NATURAL AREA ASSETS

The former primary school use on the LSP area has informed the structure and composition of the site's environmental and landscape features, which consist primarily of large cleared areas of planted lawn with stands of parkland cleared trees. Remnant vegetation exists surrounding the pad sites of the former primary school buildings and oval. The eastern side of the LSP area, which served the purpose of the former oval playing field is generally cleared and flat.

The LSP area is not affected by any statutory environmental listings of significance.

An environmental assessment was conducted to identify potential fauna species that may inhabit the site. It was concluded that the existing trees in the LSP area may be visited opportunistically by native birds moving through the Joondalup landscape. However, the assessment considered it unlikely that the trees would be used exclusively by native fauna species on a permanent basis.

The majority of scattered trees on the site are jarrah, marri, and coastal moort. A tree assessment was conducted by a specialist arboriculturist to identify trees worthy of retention. The assessment considered the health, structure, and species suitability. Generally, trees of significance are contained within the central spine, north-east corner of the LSP area, and with southern boundary abutting the existing residential landholdings.

The environmental overview makes the following key recommendation for the LSP area:

Retain the remnant native trees (through a combination of placing urban development in cleared land and the retention of trees eg. In POS and road reserves etc.)

Refer Figure 5, Trees of Notable Value.

FIGURE 5: TREES OF NOTABLE VALUE



PART TWO: EXPLANATORY SECTION

Refer Appendix 3, Arboriculture Assessment.

2.2 LANDFORM AND SOILS

The Environmental Summary Report (Appendix 3), Geotechnical Report (Appendix 4) and Local Infrastructure Servicing Strategy (Appendix 6) have been used to inform this section.

Generally, the landform and soils are conducive to the accommodation of urban development.


2.2.1 Landform

The topography of the LSP area is generally uniform with the gradient slightly decreasing from approximately 37.6m AHD (Australian Height Datum) in the site's south-west to a minimum of approximately 33.4m AHD in the north-east and north west corners. Level pad sites are present where the former buildings associated with the past primary school use were located.

In addition, the site had been levelled for the former school playing field located within the east of the LSP area. To allow for the levelling there is a small embankment on the western edge of the oval which is situated relatively central to the LSP area.

Refer Figure 6, Elevation Plan

FIGURE 6: ELEVATION PLAN



PART TWO: EXPLANATORY SECTION

2.2.2 Soils

The LSP area sits upon the Spearwood Dune system, which generally consists of yellow/grey sands over limestone. Specific to the LSP area, a Geotechnical Report proposed for the LSP area confirms the following soil composition:

- Topsoil – dark brown to grey brown sandy topsoil with some silt and some rootlets to a general depth of 0.1 metres.
- Filling (Sand) – loose to medium dense, yellow-brown and grey-brown to grey, sand filling to depths of between 0.2 to 1.2 metres.
- Sand – Loose to medium density, dark grey to yellow-brown, sand with a trace of silt to test pit termination depths of between 2.5 and 2.8 metres.

The buildings associated with the former East Greenwood Primary School were removed in May and June 2011. It is possible that undiscovered services and buried fences or similar may be present within the LSP area.

Generally, the LSP area is capable of accommodating residential urban development which includes minor cut and fill site works. The Geotechnical Report makes some recommendations for construction techniques that can be implemented and enforced at the detailed design phase.

Refer Appendix 5, Geotechnical Report.

2.2.3 Acid Sulfate Soils

The Department of Environment's Risk Mapping indicates that the entire extent of the LSP area has no known risk of acid sulfate soils occurring within 3 metres of the natural soil surface.

2.3 GROUNDWATER AND SURFACE WATER

No surface water features exist within the LSP area.

The Department of Water's (DoW) Perth Ground Water Atlas estimates the maximum groundwater elevation across the LSP area to be between 22 and 24 metres AHD, giving a minimum clearance to groundwater of 10 metres.

The LSP area overlies the Perth Coastal Underground Water Pollution Control Area (Priority 3), which means water supply sources can co-exist with other land uses such as residential development. The development of the site is not considered to have significant pollution potential. Stormwater management and drainage to groundwater will be managed in accordance with the Better Urban Water Management Framework.

Refer Appendix 4, Environmental Summary Report.

2.4 WATER MANAGEMENT AND CONSERVATION

Pre-lodgement consultation with the DoW in November 2014 confirms that a Local Water Management Strategy (LWMS) is not necessary to support the proposed LSP, given the relative size of the proposed development coupled with the lack of water infiltration constraints within the LSP area.

Pre-lodgment consultation with the City of Joondalup confirms that the surrounding urban stormwater catchment appears to be at capacity. It is therefore necessary to retain and infiltrate a large majority of stormwater on the site, within the proposed POS area. The management of stormwater and implementation of water sensitive urban design will be formally documented in an Urban Water Management Plan (UWMP) prepared as a condition of subdivision approval, as recommended by the DoW.

Refer Appendix 4, Environmental Summary Report.

2.5 BUSHFIRE HAZARD

The subject site is not within a bushfire risk area and is generally cleared, with scattered strands of parkland trees. As such, bushfire risk is considered low.

Refer Appendix 4, Environmental Summary Report.

PART TWO: EXPLANATORY SECTION

2.6 HERITAGE AND SITE HISTORY

The site subject of the LSP area was first designated a government primary school site in the late 1960s, during the time the Parin family first subdivided and developed the Greenwood locality. The East Greenwood Primary School serviced the immediate surrounding community for more than four decades, and had an active Parents and Community Group (P&C Group) and strong teaching staff. A few of the teaching staff serviced the school for a period of 20+ years, with some valued staff teaching for around 40 years at the former school.

The community consultation process (detailed in the forthcoming sections) recorded many historical memories of the former use. Many community members recognised significant sports carnival events, local sporting events such as football and soccer, P&C meetings, school concerts and fetes, and various fundraising efforts for school amenities, such as the kiln for the art room and local business involvement. The community also recognised the works of a former notable school pupil who has excelled to become a leading Australian Cartoonist, writing and drawing the Australian comic strip *Ginger Megs*.

In 2007, the Minister for Education and Training announced that East Greenwood Primary School and Allenswood Primary School would be replaced by one new school collocated on the Allenswood site (to be known as Greenwood Primary School). This would result in the East Greenwood Primary School site being surplus to the DET needs. The East Greenwood Primary school was closed toward the end of the 2010 school year after completion of the new Greenwood Primary School in late 2010.

The site was sold to the Department of Housing and rezoned in 2010 to allow for residential development, subject to an endorsed local structure plan.

Refer Figure 7, Historical Photographs of Former East Greenwood Primary School.

FIGURE 7: HISTORICAL PHOTOGRAPHS OF FORMER EAST GREENWOOD PRIMARY SCHOOL



PART TWO: EXPLANATORY SECTION

2.7 EXISTING AND SURROUNDING COMMUNITY

Development of the area dates primarily from the late 1960s, with rapid growth taking place during the 1970s. The population has declined since the early 1990s, as a result of relative stability in dwelling stock and a decline in the average number of persons living in each dwelling.

Analysis of the age structure of the Greenwood population in 2006 compared to that of the City of Joondalup shows that there was a smaller proportion of people in the younger age groups (0 to 17) but a larger proportion of people in the older age groups (60+).


As an area like Greenwood ages, more housing stock is freed up through migration and mortality enabling families to re-populate these areas. Family breakups can also result in single parent families and lone person households seeking out affordable and suitable housing options. The process of regeneration occurs most readily in areas that have managed to minimise loss of family services and that can adapt by developing a diversity of housing stock suitable to a wider variety of household types.

Development of the LSP area therefore provides the opportunity to target a niche infill market within Greenwood, particularly as empty nesters and lone person households look to upgrade to a newer home and/or downsize their family size dwellings.

Figure 8 provides a snapshot of the demographic analysis process used to gain a better understanding of existing and future housing needs in Greenwood. The principal conclusion that can be drawn from the analysis is the significant potential for development of the LSP area to assist in creating housing opportunities for a broader range of people. The key groups identified include:

- Couples and singles with no children.
- First home buyers.
- Downsizers, particularly those in the area looking to upgrade to a new dwelling.
- Single parent families.

FIGURE 8: UNDERSTANDING LOCAL HOUSING NEEDS



PART TWO: EXPLANATORY SECTION

2.8 COMMUNITY CONSULTATION

2.8.1 Overview

On 28 June 2011, a petition was submitted to Parliament with 847 signatures requesting up-front early consultation, following some community concern with the redevelopment of the East Greenwood Primary School site. As part of the tender process, the DoH requested that any potential development partner would undertake community consultation to the satisfaction of the City of Joondalup. To date, Australand has been committed to exceeding its LSP statutory obligations in this area, with a rigorous community consultation programme implemented since its appointment.

At the time in which the LSP area was rezoned to Urban Development, it was originally agreed with the City of Joondalup that community consultation would take place prior to the submission of the LSP. A Community Consultation Plan was prepared and agreed to by the City, consisting of:

- A Community Ideas Day.
- Community feedback form collection period (opportunity for community to submit comment).
- A Community Working Group (added as a response to community requests for further feedback opportunity).

On the 2nd August 2014 a Community Ideas Day was held in accordance with the terms of the agreed plan.

The forum was well attended by approximately 150 community members and a significant amount of feedback was gathered to assist the development of the LSP.

In addition to the community's input in relation to the design of the project there was considerable community feedback about the process of consultation and in response to that feedback the proponents resolved to undertake further refinement to the plan to increase the depth and local relevance of the consultation. This resulted in the establishment of the Greenwood Working Group, the role of which was to provide input into the development of the LSP.

Beyond the scope of the agreed Community Consultation Plan, Australand implemented the following initiatives.

- A facebook page for community members to share comments and provide feedback.

- A dedicated website devoted to providing information to the community, including a full time community liaison service for all enquires via phone or email.

In its entirety, the community consultation process resulted in a number of community members participating in the following manner:

- Approximately 150 local community members participating in the Community Ideas day held on 2 August 2014.
- 51 Feedback forms totalling almost 1000 comments being submitted by 9 September 2014.
- 22 Working Group EOI forms being submitted and a selected Working Group of 12 community members.

Refer Appendix 2, Consultation Plan, Community Feedback Summary, and Working Group Session Minutes.

2.8.2 Vision and Objectives Presented to the Community

From its inception, the aim of the project has been to deliver a quality housing development that enhances the quality of life for the existing Greenwood community and future residents.

A project vision was presented at the Community Ideas Day - A Village in the Green. The vision is to achieve a fusion between the leafy and spacious sense of place that is "Greenwood" and the more urban character that the proposed housing choices will bring. It is underpinned by four key objectives:



PART TWO: EXPLANATORY SECTION

2.8.3 Community Ideas Day and Public Consultation Period

On 2 August 2014, a Community Ideas Day was held at Warwick Leisure Centre which attracted approximately 150 local community members. The ideas day format was intended to be an informal setting where community participants could receive and share important information, engage and contribute ideas to the design of the LSP. Importantly, the design of the forum was not a 'design and defend' exercise, rather the focus was on community contribution in-lieu of a formal draft plan being completed for the LSP area. Community participants were provided with the opportunity to speak with the project team, and give feedback on the broad vision and ideas that were presented.

Community sentiment was captured in the following manner:

- Comments collected on post-it notes from the participants.
- Comments collected from feedback forms lodged on the day and within a one month feedback period – total 51 forms submitted.
- The Greenwood East Working Group Community Facebook page and email address was established, which was used to keep the conversation going, and to respond to community enquiry.

Community feedback was summarised according to the four objectives of the vision. This enabled a more rigorous testing of the vision and provided a framework for balancing project objectives with community desires.

A total of 966 comments were received from the above processes, which are summarised in Table 2.

TABLE 2: COMMUNITY FEEDBACK SUMMARY

HOUSING CHOICES	39.9 % _commented on density and land use	
GREAT PUBLIC SPACES	36.1 % _commented on open space, recreation and nature	
HIGH QUALITY DESIGN	12.3% _commented on height, layout of site and built form	
NEIGHBOURHOOD CHARACTER	11.7% _commented on traffic, parking and pedestrian safety	
966 Total Comments received	approx. 150 estimated participants at Ideas Day	51 Total feedback forms received

PART TWO: EXPLANATORY SECTION

2.8.4 Greenwood East Working Group

Following the feedback received during the community consultation process – specifically, the request for more opportunities for involvement – a Community Working Group was established. An aim of the Working Group was to capture the representative views of a suitable cross-section of the community, particularly those who live closest to the site, through an EOI process. Of the 22 EOI forms that were submitted, a total of 12 members were selected to form the Greenwood East Working Group. The selection was based on a number of factors including age, gender, address relative to the site, representation of local community associations, availability, and consideration of justification submitted. The Working Group sessions were run by independent facilitators, Estill Associates, and observed by City of Joondalup Councillors John Chester and Brian Corr.

Refer to Appendix 2 for detailed minutes and agenda.

The objective of the Working Group was:

To provide input to the development of the emerging Structure Plan for the East Greenwood Primary School site redevelopment.

The 12 Working Group members collaborated in a transparent, and open manner to help the project partners better understand and address key community issues. An invaluable understanding of local needs and aspirations was gained as a result of the process.

Two Working Group sessions occurred following the Community Ideas Days and at the conclusion of the feedback period. The first session occurred on 30 September 2014. Following feedback received during the Ideas Day and via feedback forms, the vision was developed with Working Group in the following key areas:

- Commitment to no 4 storeys buildings.
- 1 and 2 storeys buildings around the edge of the site.
- Potential for substantial mature tree retention.
- Better understanding of district traffic issues gained.
- Spreading vehicle access points around surrounding streets.
- Architecture responsive to the surroundings.
- Interpretation of school history.

The second session occurred on 13 October 2014. Following feedback from the Working Group at the first session, issues were addressed and the vision refined as follows:

- Overlooking – a 12m tree protection zone was established on the rear boundary and commitments made on minimum window heights.
- Public Open Space – 13% provision, over and above the 10% requirement.
 - native landscaping and recycled brick and timber ('rustic') materials in open space.
- Yield estimate provided at 115 – 135 dwellings.
- Potential parking locations shown, including on lots, visitor parking and Cockman Park parking.
- Examples of garbage bins in lanes and the desired lane character provided as requested.

The Working Group raised concerns with the intersection proposed at the time near the corner of Mulligan Drive and Reilly Way. They also requested more design detail in the LSP, both of which have been addressed in this report.

2.8.5 Key Outcomes from Community Consultation Process

A concept plan was presented at the conclusion of the second Working Group Session. The twelve members were surveyed independently on their level of support for the plan, the results of which represent a key outcome of the consultation process, in particular, that none objected nor strongly objected to the plan:



A summary of the community feedback and key outcomes resulting from the aforementioned processes are shown in Table 3 opposite.

PART TWO: EXPLANATORY SECTION

TABLE 3: COMMUNITY FEEDBACK AND LSP RESPONSE

COMMUNITY FEEDBACK	RESPONSE	ACHIEVED
HOUSING CHOICE		
The community has sought clarification on the level of social housing to be provided in the project.	The project will provide 1 in 9 dwellings for social housing, including catering for the needs of elderly, people with disabilities and single parent families.	✓
Community feedback suggested that there are residents looking to downsize to low maintenance properties within Greenwood	Australand will be proposing low maintenance dwellings to suit this buyer profile.	✓
Community feedback suggested that the development should allow for people to age in place without having to live in a retirement village	Some single storey dwellings that are adaptable to allow for people to age in place will be proposed.	✓
Feedback was received that housing opportunities should be made available at price points accessible to First Home Buyers	An array of housing options will be incorporated that will allow people on low to moderate incomes to acquire a property in proximity to their families and friends.	✓
The community expressed a desire to see a range of dwelling types provided	The project is proposing 1, 2 and 3 bedroom product in the form of single storey and double storey homes, as well as apartments.	✓
PUBLIC OPEN SPACE		
The community wanted surety that 10% public open space (POS) would be provided	Australand is aiming to achieve a provision of approximately 25% of POS, well above the 10% POS required.	✓
The community wants to see the retention of native vegetation and for implemented vegetation to be predominantly native	Predominantly native vegetation and landscaping that fits in with the existing trees to be retained on site will be included.	✓
The community expressed a desire to retain trees on site and located their preference for retention at the Community Ideas Day	Comments have been taken on board and the developer is proposing to retain a significant number of trees in the north west corner, centre and near the southern boundary of the site in accordance with community feedback.	✓
The community expressed a desire that the POS should be useable by all local residents and not just those within the development	The POS will be accessible to all residents with pedestrian connections being provided through the site down to Cockman Park	✓
The working group do not want to see public toilets within the POS	Public toilets within the public open space will not form part of the landscape proposal.	✓
Members of the community expressed a desire to see some form of interpretation of the sites former use as a primary school in the landscaping	The developer will be looking to identify a former school building footprint, incorporate a new playground and other opportunities to celebrate the social history of the site as part of the development.	✓
The community expressed a desire to see sustainability incorporated into the built form outcomes	Australand will be assessing the project against the Green Building Council "Greenstar Communities" rating tool and also setting minimum NATHERS ratings for the environmental performance of individual homes.	✓

PART TWO: EXPLANATORY SECTION

COMMUNITY FEEDBACK	RESPONSE	ACHIEVED
HEIGHT AND DENSITY		
The community strongly objected to 4 storey apartments	There will not be any 4 storey apartments anywhere on the site.	✓
The community expressed concern around the inclusion of apartments	This feedback has been taken on board. Only two locations are proposed for 3 storey apartments around the central open space area, away from the edges of the site.	✓
The community expressed concerns about privacy and overlooking onto housing that fronts Dargin Place and backs directly onto the development	Minimum rear setbacks have been increased to 12m with second storey windows to be a minimum height of 1.65m from floor level to prevent overlooking. A protection zone has also been introduced to ensure the existing trees are retained.	✓
Some community feedback suggested that there should not be any dwellings above 1 storey along Dargin Place, Reilly Way or Mulligan Drive	The existing surrounding zoning allows 2 storey houses. Notwithstanding Australand have taken this feedback on board and houses around the outside edge of the project area will be predominantly single storey.	✓
The community expressed a desire to see artist's impressions as part of the LSP submission.	Artist impressions will be provided as part of the Local Structure Plan submission.	✓
TRAFFIC		
The community expressed concerns about the additional traffic placed on the neighbouring streets	As agreed through the Working Group process the project will provide street and lane connections to all street frontage to disperse traffic. The LSP will contain a traffic assessment which will compare the traffic volumes to the previous school use and address the relative effect on the wider street network including the Cockman and Warwick Road intersection. The resultant traffic will be equivalent to the site's former use.	✓
The community does not want to see roads connecting through the site that promote rat-running	The street network will be designed to ensure outside traffic does not short-cut through the site.	✓
The community, including residents directly adjacent to the site, did not want to see crossovers along Dargin Place, Reilly Way and Mulligan Drive	The proposed dwellings will be provided with rear lane access. This will allow houses to front the existing streets with generous landscaped verges. Garages, bin collection points and other services will be kept from view in the rear laneways.	✓
The community expressed concerns about placing an access/egress point near the intersection of Reilly Way and Mulligan Drive due to pre-existing traffic issues.	The proposed access point near the intersection of Reilly Way and Mulligan Drive has been removed.	✓
The community expressed concerns around the provision of visitor parking	Visitor parking will be provided throughout the site and above the minimum required standards.	✓

PART TWO: EXPLANATORY SECTION

3.0 LAND USE AND SUBDIVISION REQUIREMENTS

3.1 SUSTAINABLE DEVELOPMENT OUTCOMES

From its inception, the Australand and Department of Housing partnership established a corporate commitment with the intent of delivering a development that delivered best practice sustainable outcomes for the East Greenwood community. That is, due consideration given to economic, social, and environmental design attributes in the interest of serving current and future demographics. The necessity for a sustainable development outcome was predicated through the community consultation process.

The intent of the detailed design is to deliver a range of housing products to best cater for a wide variety of household structures. This approach ensures the current gaps in available housing stock are addressed, including couples and singles with no kids, first home buyers, downsizers, and single parent families.

The inclusion of a rigorous community consultation process ensures that social factors are not only considered, but solutions and outcomes are suggested by the community for the community.

TABLE 4: SUSTAINABLE DEVELOPMENT OUTCOMES



PLACE

Active community development program for new and existing residents
Celebrated history of learning in the public domain and community life
'Success' and 'achievement' school motto reflected in the quality of housing and community
Diverse character responsive to sub-urban context and broader opportunities



HOUSING

Affordability Significant portion of housing priced below the Greenwood median
Choice of up to 20 housing options in response to demographic analysis
Lifelong housing through adaptable housing design and downsizing options
Architectural quality balancing unity and variety



BUILDING MANAGEMENT

Construction Management initiatives to minimise disruption, nuisance and noise
Waste reduction, through construction of new dwellings
Recycling of unretainable trees
Environmental Management Plan to address vegetation and stormwater



ACCESS

Public accessibility with about half of the site accessible to the public
Inclusiveness from high visual and physical permeability
Neighbourhood connectivity enhanced for walking and cycling
People place designed for priority over vehicles



LEARNING

Generous open space provision, double the standard requirement
Existing activities enhanced including car parking, dog walking and active recreation
Safety and Security achieved through the application of CPTED principles
A proud community empowered to achieve greatness, collectively and individually



HEALTH

Active living including walking, cycling, exercise circuits and kick about areas
Mental well being supported via socially dwelling engaging frontages and spaces
Ageing in place improves health, well being and life expectancy



ECOLOGY

Biodiversity and carbon capture through significant tree retention and POS
Water wise households and public landscapes
Waste reduction during building construction
Energy Efficiency Average 7.0 star NaTHERS
Greenstar communities, rating minimum 4 star rating for the development




GOVERNANCE

Understanding stakeholders through a robust Community Plan
A community vision for the site shaped through genuine community engagement
Speed to market through streamlined approvals and Australand's experience

PART TWO: EXPLANATORY SECTION


3.2 URBAN DESIGN PRINCIPLES



GREEN LINKS


Complementary to the project vision is the notion of 'keeping the green in Greenwood'.

The layout and placement of open space has been predicated by the need to retain trees of high aesthetic, cultural, and environmental value. These trees generally fall within the central park, the north west of the open space, and within private landholdings abutting residential properties to the south. The trees of high retention value located within the residential private landholdings will be protected by ensuring building envelopes do not encroach, through the creation of a 'tree protection zone' which will be incorporated into a future Local Development Plan.



VILLAGE GREEN FOCUS

In accordance with the project vision, the intent is to provide an urban village within the green. The central park becomes the focal point for the village, and creates a distinct community meeting place and local identity. The design's intent is to ensure the green space is open and accessible to the entire Greenwood community.




CONTEXT SENSITIVE INTERFACES

Consideration to interface treatments has been paramount to the resultant design. Generally, three key interface conditions have been established, including:

- Adjoining rear boundary to the south and response to abutting residential properties.
- Fronting existing streets.
- Fronting village green directly.

Each requires a context sensitive response, particularly to building height, setbacks, articulation, architecture, landscape and civil engineering.



PEOPLE PLACE

The public open space provision well in excess of what the 10% requirement will create significant community benefits, particularly given the focus on quality and meeting local needs.

Greenwood has been designed for people first and cars second. This is best reflected by the almost completely vehicle free green links through the site, which is made possible by rear lanes. Lanes also enhance the streetscape on external streets. Visitor parking will be provided well in excess of requirements.



BUILT FORM DIVERSITY

The immense housing choice proposed for Greenwood will translate into diverse built form and immersive streetscapes.

A significant variety of housing choices will be available, ranging from 1 bedroom studio apartments to 3 bedroom, two bathroom double storey homes.



PASSIVE SURVEILLANCE

Over 60 dwellings will front the central open space, providing surveillance of this area and adjoining car parking. Defined sight lines and placement of activity in the open space is expected to reduce opportunities for crime. Lanes have been designed in accordance with Liveable Neighbourhoods and each have visible site lines from outside the site. Studio apartments have been placed with the intent of providing surveillance over laneways.

PART TWO: EXPLANATORY SECTION

3.3 ILLUSTRATIVE MASTERPLAN

The Illustrative Masterplan is a product of significant community involvement and participation. The masterplan outlines the general intent for the LSP area, based on the aforementioned design principles. High quality architecture and public realm treatments are paramount to the masterplan's success.

Refer Figure 9, 10 and 11.




FIGURE 9: ILLUSTRATION OF VILLAGE GREEN

LEGEND

- 1 Storey
- 2 Storey
- 3 Storey



FIGURE 10: ILLUSTRATIVE BUILDING HEIGHTS PLAN

PART TWO: EXPLANATORY SECTION

FIGURE 11: ILLUSTRATIVE MASTERPLAN



Key Features

1. Studios above garages provide passive surveillance and housing choice
2. School classroom footprint frames new playground and interpretation of historic uses
3. Deeper lots, double storey housing and retained trees on southern boundary provide buffer to existing housing
4. Variety of seating, including shaded picnic facilities and barbecue
5. More urban two and three storey housing overlooking Village Green
6. Views through lanes for passive surveillance
7. Pinch point designed only for the circulation of garbage trucks. Pedestrian friendly treatment
8. Subtle definition of public / private interface
9. Softening of lanes through pot plants and shrubs
10. Increased front setbacks opposite existing homes
11. Gaps between buildings

PART TWO: EXPLANATORY SECTION

3.4 BUILT FORM AND DELIVERY

The three broad target demographics will comprise a wide range of the existing Greenwood community (demographic segments), as shown in figure 12. This mix of household types requires equally diverse housing choices and hence built form outcomes. Up to 20 different housing types are proposed, the variety of which is illustrated in figure 13, including single storey built form (shown faded back) fronting existing homes.

A limited number of three storey apartment buildings frame the central park. The built form is designed in a contemporary architectural style, which provides variation in the street facades and rooflines.

In order to cater for a variety of demographics and household structures, and in the interest of housing affordability and opportunity, the resultant housing product and lots are generally smaller than the established housing stock surrounding the LSP area. In response to this, the design ensures adequate setbacks from the street to create a natural landscape buffer, building upon the green ethos reckoning. Variations in height and architectural style also assist in creating a streetscape that best responds to the established built form and contextual setting.

Refer to Figures 12, 13, 14 and 15.

The concept developed consists of 95-100 lots that accommodates an expected 115-135 dwellings. It is expected the development will provide a place of residence for 250-270 people.










		DEMOGRAPHIC SEGMENTS								
TARGET DEMOGRAPHICS										
		MIXED FAMILIES	PRE-SCHOOL FAMILIES	PRIMARY, SECONDARY SCHOOL FAMILIES	PRE-RETIREMENT DOWNSIZER	SHARED LIVING	SINGLE PARENTS	COUPLES	DIVORCEES	SINGLES
FAMILIES (Pre-School)		✓	✓	✓		✓	✓	✓	✓	
FIRST HOME BUYERS			✓	✓		✓	✓	✓		✓
DOWNSIZERS					✓	✓			✓	

FIGURE 12: LOCAL TARGET DEMOGRAPHICS AND SEGMENTS




FIGURE 13: BUILT FORM DIVERSITY DIAGRAM. EACH COLOUR REPRESENTS A DIFFERENT HOUSING TYPE, WITH SINGLE STOREY HOUSING FADED BACK.

PART TWO: EXPLANATORY SECTION

FIGURE 14: VIEW OF VILLAGE COMMON EDGE WEST



Note: the Landscape shown above is illustrative only with the intent for water wise initiatives to be utilised, as outlined in section 3.14.

PART TWO: EXPLANATORY SECTION

FIGURE 15: DARGIN PLACE VIEW



PART TWO: EXPLANATORY SECTION

Unlike typical land developments involving multiple builders, this project will be built out completely by the Project Partners. This means that houses, streets and open spaces will be designed and delivered as a completed community. Significant community benefits will result from this approach:

1. FASTER DELIVERY

- Faster construction times minimising disruption to surrounding residents.
- New houses and public open spaces available sooner.
- Entire streetscapes completed quicker; homes, front landscapes and streets built at the same time.



2. BETTER SITE MANAGEMENT AND SAFETY

- Potential impacts of construction parking, noise, safety and traffic all co-ordinated by a single builder.
- A single point of management and contact to keep residents informed about progress and respond to any concerns.



3. MORE CAREFUL RESPONSE TO SITE FEATURES

- A comprehensive approach to existing trees and landform.
- More people-friendly spaces between housing and parks/streets.



4. COMMITMENT TO DELIVER HOUSING CHOICE

- A mix of specific housing designs that meet community needs, both now and for the future.
- Mostly housing for sale on open market, with some social housing to meet the needs of people on very low incomes.



5. HIGHER QUALITY DESIGN


- Integrated architectural design of entire streetscapes, not just individual homes.
- Control of facades; positioning of windows and treatment of front boundaries.
- Housing and park/street design that looks great and provides facilities for the community.




PART TWO: EXPLANATORY SECTION

3.5 INTERFACE WITH ABUTTING RESIDENTIAL


The LSP area is bounded by streets on all sides with the exception of the southern boundary, which abuts existing residential dwellings. Following feedback from the community, the design intent was altered to create a more appropriate interface between the proposed development and the existing residential dwellings. As demonstrated in figures 16 and 17, the use of a 12 metre setback, which preserves existing mature trees of high retention value, will address the interface issues raised by the community. The tree protection zone will be controlled through the provisions of a Local Development Plan, provided at the detailed design phase.



-  Potentially Priority 1+2 Trees retained
-  Tree Protection Zone
-  2 Storey
-  Minimum building setback from rear boundary




PERMISSIBLE DEVELOPMENT



PROPOSED DEVELOPMENT

FIGURE 16: EXISTING RESIDENTIAL INTERFACE - SECTION A

PART TWO: EXPLANATORY SECTION



-  Potentially Priority 1+2 Trees retained
-  Tree Protection Zone
-  2 Storey
-  12M Minimum building setback from rear boundary




FIGURE 17: EXISTING RESIDENTIAL INTERFACE - SECTION B

PART TWO: EXPLANATORY SECTION

3.6 OPEN SPACE AND MANAGEMENT

3.6.1 Open Space Distribution And Calculation

The design and placement of the open space considered the following key elements, identified by the community as being paramount to the developments success:

- Conserve mature trees.
- Implement native planting.
- Open space surrounding the edge of the site.
- Functional parkland with walk trails connected to the existing community and Cockman Park to the south.

Table 5 and 6 provide a breakdown of the open space calculations, in accordance with the WAPC's Liveable Neighbourhoods Operational Policy. The Local Infrastructure and Servicing Strategy (Appendix 8) contains a drainage catchment plan (Appendix B) that depicts indicative stormwater retention basins. The drainage basins shown on the plan relate to the 1 in 5 year storm event. Preliminary engineering calculations indicate that approximately 0.0502 hectares of the stormwater basins will be inundated at the 1 in 1 year storm event (classified as excluded POS, counted as a deduction). The balance of the storm water basins, being 0.0770 hectares, relates to the 1 in 5 year storm event (classified as restricted POS). As only one-fifth of the 10% open space requirement can be classified as 'restricted' (being 0.0763 hectares), 0.0007 hectares is added to the deducted POS. This results in a total of 0.0509 hectares classified as POS deductions.

As demonstrated in tables 5 and 6, a total contribution of approximately 25% open space is proposed for the LSP area, well in excess of the 10% requirement.

Refer to Figure 18, Public Open Space Provision.

Refer Appendix 8, Local Infrastructure and Servicing Strategy.

TABLE 5: PUBLIC OPEN SPACE SCHEDULE

POS Area	Total area (ha)	Unrestricted	Restricted	Excluded
A	0.8291	0.7811	0.0480	0.0322
B	0.1116	0.0896	0.0220	0.0144
C	0.0714	0.0644	0.0070	0.0036
Total	1.0121	0.9351	0.0770	0.0502

TABLE 6: PUBLIC OPEN SPACE CALCULATIONS

Local Structure Plan Area	3.8636 ha
Total Net Site Area	3.8636 ha
Deductions	0.0509
Gross Subdivisible Area (GSA)	3.8127 ha
Public Open Space requirement @ 10% of GSA	0.3813 ha
May comprise minimum 80% Unrestricted Open Space	0.3050 ha
May comprise maximum 20% Restricted Open Space	0.0763 ha
Credited Open Space	
POS Area	
A	0.7962
B	0.0972
C	0.0678
Unrestricted Public Open Space	0.8849
Restricted Open Space	0.0763
Total Credited Open Space	0.9612
Total Public Open Space Provision	25.2 %

3.6.2 Tree Protection Zone

Some of the more significant and mature trees that were identified to be of high retention value, both by the community and the Arboriculture Assessment, are proposed to be within private landholdings along the LSP area's southern boundary. The design intent is to utilise the existing vegetation asset as a nature buffer between the existing dwellings to the south of the LSP area and the proposed development. The vegetation will provide a visual buffer to address potential overlooking concerns, and offer amenity and value to the existing and proposed residential dwellings.

To alleviate any concern that the trees retained within private landholdings may be at risk, a 12 metre wide setback zone to new housing the southern boundary abutting the existing residential lots will be created through the provisions of a future Local Development Plan.

PART TWO: EXPLANATORY SECTION

FIGURE 18: PUBLIC OPEN SPACE PROVISION



LEGEND

- Residential
- Central green and activity
- A 0.8291ha
- B 0.1116ha
- C 0.0714ha
- Total 1.0121ha**

PART TWO: EXPLANATORY SECTION

3.7 LANDSCAPE MASTERPLAN AND OPEN SPACE DESIGN

In support of achieving a high quality public realm that resonates with existing and future residents, the surrounding community and other future users of the precinct, a Landscape Master Plan was prepared by Emerge Associates. The landscape approach for the project is focussed on understanding, retaining and responding to community feedback and numerous existing site assets including topography and trees. The design will include references to the sites former school use and its links into the historic surrounding community. The project will build upon the existing streetscape character through materials, plant species, content and scale.

As identified by the Greenwood community and Working Group, the desire to preserve trees of high quality within public open space is paramount to the success of the development in the context of the vision. The location and design of the open space was predicated by the Arboriculture Assessment, which identified trees of medium and high retention value. The design will maintain the majority of these trees, which are located in the central spine and north west corridor of the LSP area.

By doing so, a naturalistic 'green link' has been created, which allows pedestrians and cyclists to traverse through the site. The green link connects Cockman Park to the south with Reilly Way to the north, including the public access way through to Ricketts Way. Native vegetation becomes the central ingredient to the open space composition which is consistent with community aspirations for the site.

The existing trees are a valuable asset to the site, creating immediate impact, shade and reflect the local flora so every effort will be made to retain them where possible. Plant species will be predominantly native species which are low in water use. More specific details on water wise initiatives are discussed in section 3.14.

The central park will become the focal point for the open space, and adjacent built form. Based on the community feedback and Working Group recommendations, a small playground, barbeque area, a shade structure, and nature play opportunities are proposed for the central park. The former school oval has left a level playing field, which is captured within the central and north west parks to provide room for a 'kick-about' area.

The community voiced its desire for the open space to contain a trail and space suitable for walking dogs. The intention is to complement the native vegetation and natural feel through the use of rustic and warmer finishes, such as recycled brick pavers and timber benches.

Finally, the community expressed an aspiration to recognise the former East Greenwood Primary School through interpretive design. Included within the public open space is an open air feature element based on the layout and floor plan of the prior school canteen. The school canteen was a community initiative in raising funding and as such is an important part of the site's past use and the current community's memory. The current proposal is to mimic the floor plan with a series of low seating walls where former building walls were once located with breaks in the proposed low walls where former doorways and windows were once located. The internal area will be devoted to public uses potentially including BBQs, educational seating, signage, low planting, paving, and small play elements.

Notwithstanding the above, any proposal for recreational infrastructure within the open space is subject to a separate development application at the subsequent planning phase, and would be subject to Council approval.

Refer Appendix 3, Arboriculture Assessment
Refer Appendix 7, Landscape Masterplan
Refer to Figure 19, Landscape Masterplan.

Native Verge



Playground & BBQ



Recycled Bricks + Timbers



Dog Walking Trails



PART TWO: EXPLANATORY SECTION

FIGURE 19: LANDSCAPE MASTERPLAN



Note: The intention is for low maintenance water wise plants to be utilized for landscaping throughout, as outlined in section 3.14.

PART TWO: EXPLANATORY SECTION

3.8 CRIME PROTECTION THROUGH ENVIRONMENTAL DESIGN (CPTED)

Crime prevention has been identified by the community as an important priority for the project, to ensure the existing high quality integrity of the Greenwood community is retained and protected

The contribution that environmental design can make to crime prevention and perceived security will be an important element in developing an overall sense of safety in the area. Specifically, the treatment of lighting, encouraging the right types of activity, designing for passive surveillance, and ensuring the design of the public realm reinforces a sense of safety can assist in achieving this outcome.

In excess of 60 dwellings have a direct outlook onto the open space, providing a range of opportunities for passive surveillance by residents of the new development. Additionally, as recommended by Elements 2 and 3 of the WAPC Liveable Neighbourhoods Operational Policy, studio apartments will book-end laneways to provide surveillance opportunities to these spaces.

Visitor and open space car parking has been carefully placed to generate activity that will further mitigate opportunities for crime. The passive design of the open space and green link can ensure that a range of activities will occur through the site.

Refer Figure 20, Passive Surveillance Analysis.

FIGURE 20: PASSIVE SURVEILLANCE ANALYSIS



PART TWO: EXPLANATORY SECTION


3.9 RESIDENTIAL DENSITY AND HEIGHT

As an outstanding opportunity for infill redevelopment, this project seeks to deliver diversity of housing embracing the potential to develop higher densities than would otherwise occur in a suburban context. Given the inner-middle location of the site in the metropolitan area, a more ambitious density outcome, reinforced by the density targets in Directions 2031 and demographic trends towards smaller households, is advocated by the City's Local Housing Strategy.

Notwithstanding, the intent of the design was to place more of the land in open space, for greater public benefit, than would normally be required. The provision of 25% open space therefore offsets the application of higher densities. This was a design response following a strong emerging theme from the community feedback, that an appropriate interface between the new development and existing built form be implemented.

Refer Figure 21, Local Structure Plan.

FIGURE 21: LOCAL STRUCTURE PLAN



LEGEND

LOCAL SCHEME RESERVES


 PARKS AND RECREATION

ZONES

 RESIDENTIAL

OTHER

 STRUCTURE PLAN BOUNDARY

 R CODES

 INDICATIVE ROAD RESERVE BOUNDARY

 INDICATIVE PAVEMENT SURFACE

PART TWO: EXPLANATORY SECTION

A range of building heights are proposed that respond closely to the context of development immediately surrounding the LSP area. Generally, a mix of single and double storeys proposed towards the edges of the LSP area and interfacing with the existing streetscapes; double storey dwellings are proposed toward the core of the LSP; and some three storey apartment buildings provided in the inner core of the LSP area framing the central park.

Density is applied in accordance with the LSP plan.

The LSP will provide a minimum of 115 residential dwellings, in a mix of housing types and land tenure arrangements.

Refer to Figure 21, Building Heights Plan.

FIGURE 22: BUILDING HEIGHTS PLAN



PART TWO: EXPLANATORY SECTION

3.10 LAND TENURE ARRANGEMENTS

Australand will deliver all built form outcomes in partnership with the Department of Housing. The majority of the development will be offered to purchasers as built-strata titles.

The central apartment lots (x4) will sit upon separate freehold (green-title) lots, with built-strata titling for individual units, car parking allocation, and common property.

The studio dwellings will be accommodated on a single freehold lot which contains two built-strata titles – one strata title for the conventional dwelling and associated car parking and storage and one for studio dwelling and associated car parking and storage. The studio dwelling and conventional dwelling contained within the lot will be classified as multiple-dwellings under the R-Codes, to allow for the studio floorspace to be located on top of a garage held in separate ownership.

The public open space will become Crown land vested in the City of Joondalup.

All roads created, including the access lanes, will become Crown land and road reserves.

3.11 EDUCATION FACILITIES

The LSP area is serviced by the Greenwood Primary School, which is a combination of the former East Greenwood Primary School and Allenswood Primary School. Greenwood Primary School is approximately 750 metres west of the LSP area. Additionally, the Marangaroo Primary School is approximately 750 metres east of the LSP area, but outside the school's 'intake area' as defined by the Department of Education.

In Semester 2 of 2014, the Department of Education's database listed 327 enrolled students for Greenwood Primary School, with a capacity for 465 students. Capacity is likely to be further expanded when grade 7 students transition to secondary education facilities in 2015.

The LSP area is serviced by the Warwick Senior High School, located approximately 1.0 kilometre to the south. In Semester 2 of 2014, Warwick Senior High School had 491 students enrolled, down from a 576 students in 2010.

The availability of education facilities is considered sufficient to adequately service proposed development.

PART TWO: EXPLANATORY SECTION

3.12 EMPLOYMENT

The LSP area is 17 kilometres north of the Perth city centre and 9.5 kilometres south of the Joondalup city centre. Both provide substantial employment opportunities and are accessible via the existing road network and Greenwood Train Station with connecting services.

The LSP area is in between the major strategic employment areas of Wangara, 2.6 kilometres to the north, and Balcatta, 3.5 kilometres to the south.

The LSP area is within the Kingsway Shopping Centre retail and employment catchment. Kingsway Shopping Centre is approximately 800 metres to the north east of the LSP area. A small light industrial precinct is located 400 metres north of the LSP area, on the corner of Wanneroo Road and Hepburn Avenue.

The availability of employment services is considered sufficient to adequately service a residential infill development of this nature.

Refer to Figure 2, Local Context Plan

3.13 STREETS AND MOVEMENT

This section has been informed by the Transport Impact Assessment (Appendix 6).

3.13.1 Movement network hierarchy

The LSP has been designed to prioritise pedestrian and cycle movements, allowing residents to move through the site and to access services offered within the broader locality, including transport. This has been achieved through the creation of the green link that ensures pedestrian encounters with LSP roads are minimised.

The LSP integrate with the existing local street network, and creates 13 metre road reserves (access streets) and 6 metre access lanes as depicted in the street network plan. The effective width of the access lanes will be between 8m and 10 metres achieved through garage setbacks. This will create a larger space for landscaping and amenity. The rationale behind this is for the setback areas to be maintained by private landowners as opposed to creating a maintenance burden for the City of Joondalup.

The existing road network hierarchy can be described as follows:

Street	Classification	Carriageway width	Pedestrian path
Cockman Road	Distributor B	9.4 metres (2m median)	One side only – 1.2 metres
Mulligan Drive	Access Road	7.2 metres	One side only – 1.2 metres
Gorman Road	Access Street	9.8 metres (1.8m median)	One side only – 1.2 metres
Reilly Way	Access Street	7.2 metres	One side only – 1.2 metres
Dargin Place	Access Street	7.2 metres	One side only – 1.2 metres

Refer to Figure 23, Movement Network Hierarchy Plan.

PART TWO: EXPLANATORY SECTION

FIGURE 23: MOVEMENT NETWORK HIERARCHY PLAN



FIGURE 25: STREET SECTION (ACCESS STREET D MINIMUM WIDTH)





FIGURE 24: TYPICAL LANE CHARACTER



FIGURE 26: TYPICAL LANE SECTION



PART TWO: EXPLANATORY SECTION

3.13.2 Pedestrian

The pedestrian network will provide a high level of accessibility and connectivity for pedestrians within the LSP area including connections to major external nodes. The relatively low traffic volumes on the existing surrounding street network and the estimated volumes for the proposed street network will allow pedestrians to safely and easily navigate the development crossing streets as desired.

3.13.3 Cycling

Shared paths will replace existing footpaths on external streets, connecting with the existing and proposed bicycle network. Recreational cycling has been planned for within the proposed green link and open space. Due to the low levels on anticipated traffic on the proposed street network, and the design that encourages traffic calming, cycling can also be safely accommodated on the proposed streets and lanes.

3.13.4 Public transport

Transperth bus service 447 and its bus stops on Cockman Road are within 400 metres of the LSP area. Transperth bus services 389 and 450 and its bus stops are located on Wanneroo Road, within 600 metres walking distance to the east of the LSP area.

Refer to Figure 24, 25, 26 and 27.

FIGURE 27: PEDESTRIAN & CYCLING OPPORTUNITIES PLAN



PART TWO: EXPLANATORY SECTION

3.13.5 Private vehicles and traffic

The access system has been developed carefully to share traffic generated from the LSP area between the surrounding streets and intersections. In terms of volume, traffic estimates predict a total of 670 daily vehicular trips be generated from the development, including 63 trips during the PM peak weekday period. By comparison, the former school use generated approximately 742 total daily vehicular trips. Accordingly, the existing and proposed local road network will be able to support traffic generated from the proposed development.

Refer Appendix 6, Traffic Impact Assessment.

3.13.6 Parking

All household car parking will be accommodated on-site within individual private land holdings. Visitor car parking is located to service the proposed dwellings and to provide opportunities for surveillance. The concept design provides car parking well in excess of the one visitor parking bay per four dwellings that would be required if the site works built out for a grouped dwelling (survey-strata) development.

Refer to Figure 28, Parking.

FIGURE 28: PARKING



PART TWO: EXPLANATORY SECTION

3.14 WATER MANAGEMENT

In developing the storm water drainage design the intention is to incorporate appropriate Water Sensitive Urban Design and drainage best management practices for storm water and nutrient management at the site. This is to ensure there will be no unacceptable impacts on the existing local drainage infrastructure or the environment and that the site is protected from flooding.

Water wise processes for consideration at detail design stage of the process and subject to Council approvals may include water wise planting species, hydrozoned irrigation, use of rain sensors and water meters, use of alternate hardscape materials, minimized turf areas, use of low loss irrigation nozzles, soil amendments, porous surface treatments, additional mulching, storm communal bores, third pipe irrigation for private areas, water harvesting and reuse where viable.

One of the advantages of providing higher densities within the LSP area is that it allows for larger areas to be allocated for open space, creating sound opportunities for infiltration and retention on-site through permeable surfaces. This will be accomplished by utilising current best urban water practices within the development. Water for irrigation will be undertaken to promote cost effective water efficient practices through the open space designs.

The drainage design indicates a series of smaller catchments with a range of treatments including subsurface storage located under parking areas and smaller planted swales to capture and treat 1:1 flood events. 1:5 and 1:10 events may spill into open grass areas and will be held back from residential lots via slope and raised pad sites. The 1:100 drainage event will be managed off site via various head works.

3.15 INFRASTRUCTURE COORDINATION, SERVICING AND EARTHWORKS

3.15.1 Site Works

Demolition of the primary school buildings occurred between May and June 2011. While the surface of the site has been remediated, it is possible that undiscovered services, buried fences or similar may be present. As such, unexpected finds protocols are recommended as part of the construction works. Additionally, it is recommended that a forward works scope is implemented to reduce the risk of cross contamination for any existing services uncovered during the civil works process.

Refer Appendix 8, Servicing Strategy.

3.15.2 General earthworks

The site will be earthworked with the intent to minimise import fill requirements, improve lot accessibility and maximise the retention of trees. Construction of retaining walls are required to ensure level building sites with specific planning and engineering consideration to minimise walls of significant height i.e. greater than 3m. Stair access will also be provided where required for lots with rear laneway access and fronting public open space.

A construction management plan, required as part of the subsequent detailed design application phase, will outline the intention and scope for the proponent to organize waste collections during the different stages of construction.

Refer Appendix 8, Servicing Strategy.

3.15.3 Infrastructure coordination and servicing

Wastewater

The LSP area is capable of being serviced by the existing reticulated sewer infrastructure, subject to the appropriate headworks charges and negotiations through the Water Corporation.

Water Supply

The LSP area is capable of being serviced by the existing reticulated water infrastructure, subject to the appropriate headworks charges and negotiations through the Water Corporation.

PART TWO: EXPLANATORY SECTION

Power Supply

The LSP area is capable of being serviced by power infrastructure through Western Power, the service provider. In accordance with Western Power policy, all new development will need to be serviced by underground three phase power. As such, some of the existing infrastructure immediately surrounding the LSP area may need to be converted to the underground system.

Gas Supply

The LSP area is capable of being serviced by the existing gas supply infrastructure, subject to the appropriate headworks charges and negotiations through ATCO Gas.

Telecommunications

The proposed development subject of this LSP falls within the Australian Government's National Broadband yield criteria, which aims to reticulate communication assets to all new developments over 100 lots. There may be some specific easements that will need to be considered at the detailed design stage.

Stormwater

The LSP area has excellent infiltration qualities, of which the design takes advantage of spatially through the application of large open space areas. As such, The LSP area is capable of accommodating the majority of stormwater onsite. Stormwater will generally be accommodated in a series of basins, where infiltration is not possible.

Refer Appendix 8, Servicing Strategy.

3.16 DEVELOPER CONTRIBUTION ARRANGEMENTS

No extraordinary provisions are planned for in relation to development contributions. The proposal is likely to attract the standard requirements typical of a development of this nature.

3.17 IMPLEMENTATION

3.17.1 Further documentation and management plans

To facilitate subdivision and development of the land, further studies and/or management plans are to be prepared, as applicable, to the satisfaction of the relevant authority as outlined in Table 6.

TABLE 6: FURTHER DOCUMENTATION AND ACTIONS

Documentation	Approval Stage	Approving Authority
Local Development Plan/s (for all lots)	Lodged prior to building permit stage, managed as a condition of subdivision approval.	City of Joondalup
Urban Water Management Strategy	Lodged prior to building permit stage, managed as a condition of subdivision approval.	City of Joondalup; Department of Water

3.17.2 Land assembly

The site subject of this LSP is ready for development and owned by the proponent for these purposes.

3.17.3 Indicative staging

The LSP area will generally be delivered in either one or two stages, depending on market demand. The intention is deliver the development with as little interruption and impact the surrounding community as possible. Given the ample space the site offers, it is considered that development will be able to achieve this with relative ease, subject to the appropriate management measures being in place at the detailed design phase.





RobertsDay
planning·design·place

level one
130 royal street east perth
wa australia 6004
t+61 8 9218 8700

33 chessell street
south melbourne
vic australia 3205
t+61 3 9645 0788

level four
17 randle street surry hills
nsw australia 2010
t+61 2 8202 8000

robertsday.com.au